




NOTES:

Holes will be permitted in the outer $\frac{1}{2}$ of the web for wire, rings, etc. Tie web to #3 reinforcing bars @ 12 maximum intervals to support the waterstop in proper position during concrete placement. Alternative detail may be submitted for approval of the Engineer.

Waterstop to have 5 or more pairs of of raised ribs to provide 0.1 square inches minimum rib cross-section area on each half of the waterstop.

1/8"



C. One cubic foot pervious backfill material in a nonwoven filter fabric, securely tied.

D. Pervious backfill material continuous behind retaining wall or abutment.

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

BRIDGE DETAILS

NO SCALE

BO-3